

Force Engineering & Testing

19530 Ramblewood Drive
Humble, Texas 77338
Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com

Product Evaluation Report
SUNSHINE METAL SUPPLY, INC.

1 1/2" Mechanical Lock, 24 Ga. 16" Wide Roof Panel over Plywood

Florida Product Approval # 18386.1 R4

Florida Building Code 2023

Per Rule 61G20-3

Method: 1 -D

Category: Roofing

Subcategory: Metal Roofing

Compliance Method: 61G20-3.005(1)(d)

HVHZ

Product Manufacturer:

Sunshine Metal Supply, Inc.

719 Cattleman Road

Sarasota, Florida 34232

Engineer Evaluator:


Johnathan Green, P.E. #88223


Florida Evaluation ANE ID: 12901

Contents:

Evaluation Report: Page 1 - 4


Installation Detail: Page 5 - 14


SEP 28 2023



THIS DOCUMENT HAS BEEN DIGITALLY SIGNED AND SEALED BY JOHNATHAN GREEN ON THE DATE ADJACENT TO THE SEAL.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



Compliance Statement: The product as described in this report has demonstrated compliance with the Florida Building Code 2023, Sections 1504.3.2, 1518.9, 1523.6.5.2.4.

Product Description: 1-1/2" Mechanical Lock Standing Seam Roof Panel, 24 Ga. Steel, 16" Wide, Roof Panel restrained with steel slider clips into APA Plywood decking. Non-structural Application.

Panel Material/Standards: Material: 24 Ga. Steel, ASTM A792 unpainted or painted with Valspar Fluropon or ASTM A653 G90 conforming to Florida Building Code 2023 Section 1507.4.3.
 Yield Strength: Min. 50.0 ksi
 Corrosion Resistance: Panel Material shall comply with Florida Building Code 2023, Section 1507.4.3.

Panel Dimension(s): Thickness: 0.024"
 Width: 16" max coverage
 Rib Height: 1-1/2"
 Panel Seam: 180° Seam, Double Lock w/ mechanical seamer

Roof Panel Clips: Product Name: 1500SC, 1-1/2" Sliding Clip Assembly
 Type: Two Piece Slider
 Top: 22 Ga. Galvanized Steel
 Base: 16 Ga. Galvanized Steel
 Corrosion Resistance: Per Florida Building Code 2023 Section 1506.7

Roof Clip Fastener: (2) #12-11 x 1" Pancake Type A, 1/4" minimum penetration through plywood
 Corrosion Resistance: Per Florida Building Code 2023, Section 1517.6.

Substrate Description:

1) For HVHZ construction, use 19/32" or greater APA Rated plywood or wood plank. In reroofing applications where the deck is less than 19/32" thick (min. 15/32") the attachment of the decking in no case shall be less than 8D annual ring shank nails at 6" O.C. Design of plywood and plywood supports are outside the scope of this evaluation. Substrate must be designed in accordance w/ Florida Building Code 2023.

2) For Non-HVHZ applications, use min. 15/32" thick, APA Rated plywood over supports at maximum 24" O.C. Design of plywood and plywood supports are outside the scope of this evaluation. Substrate must be designed in accordance w/ Florida Building Code 2023.

Allowable Design Uplift Pressures:

Table "A"

Maximum Total Uplift Design Pressure:	59.75 psf	73.9 psf	81.0 psf	88.1 psf	102.3 psf	123.5 psf
Clip Spacing:	24" O.C.	20" O.C.	18" O.C.	16" O.C.	12" O.C.	6" O.C.
# Fasteners per Clip:	2	2	2	2	2	2

*Design Pressure includes a Safety Factor = 2.0.




- Code Compliance:** The product described herein has demonstrated compliance with The Florida Building Code 2023, Section 1504.3.2, 1518.9, 1523.6.5.2.4.
- Evaluation Report Scope:** The product evaluation is limited to compliance with the structural wind load requirements of the Florida Building Code 2023, as relates to Rule 61G20-3.
- Performance Standards:** The product described herein has demonstrated compliance with:
- TAS 125-03
 - UL 580-06 - Test for Uplift Resistance of Roof Assemblies
 - UL 1897-2015 - Uplift Test for Roof Covering Systems
 - TAS 100-23 - Test Procedure for Wind and Wind Driven Rain Resistance of Discontinuous Roof Systems
 - TAS 110-00 - Accel. Weathering ASTM G 155 / Salt Spray ASTM B 117
- Reference Data:**
1. TAS 125-03: UL 580-94 / 1897-98 Uplift Test
Force Engineering & Testing, Inc. (FBC Organization # TST-5328)
Report No. 72-0313T-06*
 2. TAS 100-95
Farabaugh Engineering & Testing, Inc. (FBC Organization # TST-1654)
Report No. T157-07*
 3. TAS 110-00: Valspar Fluropon coated metal panel testing
A) ASTM G 155
B) ASTM B 117
 4. Certificate of Independence
By Johnathan Green, P.E. (No. 88223) @ Force Engineering & Testing
(FBC Organization # ANE ID: 12901)
- Test Standard Equivalency:**
1. The UL 580-94 test standard is equivalent to the UL 580-06 test standard.
 2. The UL 1897-98 test standard is equivalent to the UL 1897-2015 test standard.
 3. The TAS-100-95 test standard is equivalent to the TAS 100-23 test standard.
- Quality Assurance Entity:** The manufacturer has established compliance of roof panel products in accordance with the Florida Building Code and Rule 61G20-3.005 (3) for manufacturing under a quality assurance program audited by an approved quality assurance entity.
- Minimum Slope Range:** 2:12. Minimum Slope shall comply with Florida Building Code 2023, including Sections 1515.2.2 and in accordance with Manufacturers recommendations.



- Installation:** Install per manufacturer's recommended details and RAS 133.
- Underlayment:** Per Manufacturer's installation guidelines per Florida Building Code 2023 Section 1518.2.
- Fire Barrier:** Any approved fire barrier having a current NOA. Refer to a current fire directory listing for fire ratings of this roofing system assembly as well as the location of the fire barrier within the assembly. Fire classification is not part of this acceptance.
- Shear Diaphragm:** Shear diaphragm values are outside the scope of this report.
- Design Procedure:** Based on the dimensions of the structure, appropriate wind loads are determined using Chapter 16 of the Florida Building Code 2023 for roof cladding wind loads. These component wind loads for roof cladding are compared to the allowable pressure listed above. The design professional shall select the appropriate erection details to reference in his drawings for proper fastener attachment to his structure and analyze the panel fasteners for pullout and pullover. Support framing must be in compliance with Florida Building Code 2023 Chapter 22 for steel, Chapter 23 for wood and Chapter 16 for structural loading.


*The Test Reports are owned by Metalforming, Inc. Metalforming, Inc. gives the above manufacturer permission to use these test reports.




Force Engineering & Testing

19530 Ramblewood Drive
Humble, Texas 77338
Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com


ML 150H 24 GA. STEEL PANEL






Force Engineering & Testing


19530 Ramblewood Drive
Humble, Texas 77338
Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com






Force Engineering & Testing


19530 Ramblewood Drive
 Humble, Texas 77338
 Phone: (281) 540-6603 FAX: (281) 540-9966
 Website: www.forceengineeringtesting.com






Force Engineering & Testing

19530 Ramblewood Drive
 Humble, Texas 77338
 Phone: (281) 540-6603 FAX: (281) 540-9966
 Website: www.forceengineeringtesting.com



- NOTES:
 1. MAT'L: SEE CHART.
 2. ALL BENDS TO BE ±2°.
 3. ALL RADII TO BE .06 UNLESS OTHERWISE NOTED.
 4. FOR CLARITY, BASE IS SHOWN FULLY CLOSED.


REV.	DATE	ZONE	EDR	INTAL	DESCRIPTION
L	3/11/02	5111	N/A		
(060-.068 TH) 090 CALV. STL PLAIN FINISH (SEE MPF-000) MATERIAL DESCRIPTION					
PMW	W/O	SCALANT			
SFS Inteco, Inc. 19530 Ramblewood Drive Humble, TX 77338 Phone: (281) 540-6603 Fax: (281) 540-9966 WWW.FORCEENGINEERINGTESTING.COM					
DATE	4/26/94	DESIGN	APPROVAL		
ES	NTS	DRG			
BASE DETAILS FOR TWO PIECE SLIDING CLIP					
PART NO. SD-714B					




Force Engineering & Testing

19530 Ramblewood Drive
Humble, Texas 77338

Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com







Force Engineering & Testing

19530 Ramblewood Drive
 Humble, Texas 77338
 Phone: (281) 540-6603 FAX: (281) 540-9966
 Website: www.forceengineeringtesting.com

LOW EAVE / GUTTER


- 1.) Temporarily attach gutter at ends w/ #10-12 x 1" pancake head wood screws.
- 2.) Attach cleat through gutter w/ #10-12 x 1" pancake head wood screws @ 4"oc.
- 4.) Apply a row of butyl sealant tape across the top of the cleat.
- 5.) Install panels so that the cleat is engaged into the field applied hem.






Force Engineering & Testing

19530 Ramblewood Drive
Humble, Texas 77338
Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com







Force Engineering & Testing

19530 Ramblewood Drive
Humble, Texas 77338
Phone: (281) 540-6603 FAX: (281) 540-9966
Website: www.forceengineeringtesting.com

LOW EAVE

- 1.) Temporarily attach eave trim at ends w/ #10-12 x 1" pancake head wood screws.
- 2.) Attach cleat through eave trim w/ #10-12 x 1" pancake head wood screws @ 4"oc.
- 4.) Apply a row of butyl sealant tape across the top of the cleat.
- 5.) Install panels so that the cleat is engaged into the field applied hem.







Force Engineering & Testing

19530 Ramblewood Drive
 Humble, Texas 77338
 Phone: (281) 540-6603 FAX: (281) 540-9966
 Website: www.forceengineeringtesting.com

HIGH PROFILE RAKE

- 1.) Secure rake support angle through slots w/ #10-12 x 1" pancake head wood screw @ 4"oc.
- 2.) Turn panel edge up 1 1/2".
- 3.) Apply a continuous strip of sealant tape to the inside leg of the upturned edge
- 4.) Set ledge trim on sealant tape, and secure with 1/4-14 x 7/8" HWH Tek/1 @ 12"oc.
- 5.) Apply a continuous strip of sealant tape to the top of the ledge trim.
- 6.) Install the rake trim. Secure to ledge trim with 1/4-14 x 7/8" HWH Tek/1 fasteners at 12"oc.





Force Engineering & Testing

19530 Ramblewood Drive
 Humble, Texas 77338
 Phone: (281) 540-6603 FAX: (281) 540-9966
 Website: www.forceengineeringtesting.com

HIGH EAVE

- 1.) Determine location of zee closure. Apply sealant tape to flat of panel.
- 2.) Place closure on top of sealant tape. Clamp back-up angle to bottom of panel. Secure through tape and panel with #12-14 x 1" HWH Tek/3 fastener @ 4"oc. Seal the tab of the closure to the side joints with butyl sealant.
- 3.) Apply a continuous strip of sealant tape to the top of the zee closure. Seal between ends of tape with butyl sealant.
- 4.) Install the high eave trim. Secure to closure zee with 1/4-14 x 7/8" HWH Tek/1 fasteners at 12"oc.

